BRUHAT BANGALORE MAHANAGARA PALIKE

DRAFT TENDER SCHEDULE

Name of the Work: Improvements to drains of roads next to Ayyappa temple of Jakkur Layout in ward no.07 and Improvements to drains of cross roads of Jakkur layout in ward no.07, Byatarayanapura

Sl. No.	Description	Unit	Quantity.	Rates	
				In Figures	In Words
1	Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications..	cum	599.70	137.80	Rupees One Hundred Thirty Seven And Paise Eighty Only
2	Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification	cum	107.83	5408.12	Rupees Five Thousand Four Hundred Eight And Paise Twelve Only
3	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastizers @ 3lts confirming to IS 9103-1999 RE affirmed - 2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, stair case lintels, retaining walls return walls, walls(anythickness) including attached plasters columns piers abutments pillars posts struts butresses string or lacing courses parapets copings, bed blocks , plain windows cills fillets etc., including cost of all materials labour HOM of machinery curing complete as per specifications	cum	239.85	5998.54	Rupees Five Thousand Nine Hundred Ninety Eight And Paise Fifty Four Only
4	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	tonne	14.39	75223.96	Rupees Seventy Five Thousand Two Hundred Twenty Three And Paise Ninety Six Only
5	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge	sqm	1968.00	387.96	Rupees Three Hundred Eighty Seven And Paise Ninety Six Only
6	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications.	cum	14.40	5767.46	Rupees Five Thousand Seven Hundred Sixty Seven And Paise Forty Six Only
7	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications (Data Rate Approved)	sqm	1025.00	2100.00	Rupees Two Thousand One Hundred Only
8	Providing and fixing MS Grating 260x260 mm	nos	60.00	89.00	Rupees Eighty Nine Only
9	Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1	cum	599.70	94.34	Rupees Ninety Four And Paise Thirty Four Only

DTS Approved

Executive Engineer
Project Division, Yelahanka Zone
BBMP, Bangalore - 92

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.